

**SECTION 02 41 00**

**SITE DEMOLITION**

**PART 1 GENERAL**

1.01 RELATED DOCUMENTS

- A. All of the Contract Documents, including General Agreement and Supplementary Conditions and Division 1 - General Requirements, apply to the work of this Section.

1.02 DESCRIPTION OF WORK

- A. This section describes the demolition and removal of all existing surface and sub-surface materials within the project limits as required for construction of the project.
- B. All existing utilities that are not proposed for reuse shall be demolished including those encountered and not shown on the Contract Documents.
- C. Existing utilities should be out of service before demolition is started.
- D. The Contractor shall obtain the necessary permits one (1) week prior to demolition.

1.03 RELATED WORK

- A. Section 31 22 00: Grading, Filling and Compaction

**PART 2 PRODUCTS (Not Applicable)**

**PART 3 EXECUTION**

3.01 METHOD

- A. The Contractor shall be responsible for the demolition and removal of all existing surface and sub-surface materials within the project limits as required for construction of the project. Removal of the paved surfaces shall include but not be limited to roads, curbs, sidewalks, walkways, pedestrian paths etc. The Contractor shall be responsible for full depth removal of all pavement and subsurface materials.
- B. Removal of utilities shall include but not be limited to subsurface utility lines, manholes, castings, pile supports, hydrants, valves, pipes, and boxes.
- C. Removal of miscellaneous structures and amenities shall include, but not be limited to: signs, light poles, trees, steps, shrubbery, debris, fencing, posts, conduits and incidentals.
- D. All non-salvaged material is deemed unclassified excavation and shall be demolished and disposed of off-site, legally and promptly by the Contractor.

**END OF SECTION**